



### East Midlands Airport UPS Apron Extension

**Client:**  
Galliford Try and MAG

**Completion Date:**  
November 2019

**Supplier:**  
Titan Plant Hire LTD  
PACT Concrete Testing  
Cemex

- Scope:**
- Installation of 150mm thick Lean Mix, 325mm thick Pavement Quality Concrete (PQC)
  - Total area including Airside and Landside 14,175 m<sup>2</sup>.
  - Onsite concrete batching plant with concrete transport to airside and landside work areas.
  - Onsite UKAS Concrete testing facility

#### Details:

Gill Civil Engineering Limited (GCEL) was appointed by Galliford Try to undertake the construction of new Apron for UPS facility-based East Midland airport. GCEL was responsible for the supply, UKAS testing and installation of lean mix concrete and PQC. Concrete was supplied from onsite MCM60 concrete batching plant.

The project was divided into 4 phases. Work was carried out on 6 days per week in both airside and landside environment, maintaining airport operation without disruption and meeting programme requirements.

