



Scope: Installation of Surface Water Channel of varying width

Details:

GCEL were appointed to slip-form 8500m of surface water channel of varying width (800mm and 1000mm) on central reserve and on verge at A465 Heads of Valley Section 2 project. The work comprises Slipforming V channel and gullies with the inclusion of wetformed contraction and expansion joints at regular interval. In order to meet the demand of the scheme's programme, work will be completed over various visits.

This provides logistic challenges as the work in each visit is spread across different sections resulting in stop and start work, repositioning, regular reconfiguration of slip-form paver and mould.

A465

Heads of Valley -
Section 2

Client:
Costain LTD & Welsh
Ministers

Completion Date:
April 2018

Supplier:
Hanson Concrete
Titan Plant Hire LTD

