



Scope: Installation of BBS concrete barrier to various profile

Details:

GCEL were appointed to install 4900m of BBS approved concrete barrier. The work involved installation of standard profile concrete barrier, variable profile concrete barrier, imbedded concrete barrier over 2 no. bridges, concrete barrier with base slab on raised central reserve and under bridges. The work provided logistic challenges, as it was spread across different sections miles apart and each section had its own construction detail, which required consistent reconfiguration of the slipform paver and mould. The barrier was installed on weekday & weekends to maintain highway operations.

Similar Projects: M5 (J22-23) - Central Reserve Vehicle Restraint System.

A465

Heads of Valley

Client:

Costain LTD & Welsh Ministers

Duration:

Oct 2017
Multiple Visits

Supplier:

Hanson Concrete
Titan Plant Hire LTD

